

# PARKER



## NEW FROM PARKER

### DA-750 PORTABLE MAGNETIC INSPECTION UNIT

The Parker Research DA-750 portable magnetic inspection unit provides high output AC or HWDC fields for magnetic particle inspection. Field selection is determined by using the appropriate field cable connector. Current output is infinitely variable from zero to maximum by use of the current control located on the front panel, and is indicated by the panel meter. Actual current output is determined by cable size and length.

AC magnetic fields offer the best sensitivity for detection of surface defect indications. The AC field is also beneficial for demagnetizing after inspection.

Half-Wave DC magnetic fields provide for the detection of certain subsurface defect indications. DC fields penetrate a cross section of the test area rather than just the surface. Optional magnetizing cables can be equipped with prods for circular magnetization. The cables can be wrapped around parts to form a coil for longitudinal magnetization. Demagnetization is accomplished in a similar manner.

### TR700 TRANSPORT TRUCK

Low cost folding hand truck for transporting the DA-750 or DA-1500 around the inspection area. Hang the cables on the convenient peg, store inspection media in the lower tray and you're off to the next job. The folding legs can be retracted for storage or used as a hand truck for rough terrain.

### TR700BR CABLE EXTENSION BRACKET

Can be attached to the truck to raise the cables overhead for ease of inspections.



 **Stroud Systems, Inc.**  
NDT & Hardness Testing Products Since 1962  
600 N. Shepherd Ste. 115, Houston, TX 77007  
(P) 713-861-3270 (F) 713-861-4784  
[www.stroudsystems.com](http://www.stroudsystems.com)

# PARKER

## SPECIFICATIONS

Length	17 <sup>1</sup> / <sub>4</sub> " (43.8 cm)
Width	9 <sup>3</sup> / <sub>8</sub> " (23.8 cm)
Height	8" (20.3 cm)
Maximum Output* Current	750 A, AC or HWDC
Line Voltage Single Phase	115 VAC, 50/60 Hz; 230 VAC, 50/60 Hz
Line current	27 A @ 115 VAC; 14 A @ 230 VAC
Maximum Duty Cycle	2 minutes ON 2 minutes OFF
Unit Weight	40 lbs. (18.1 kg)

\*Current ratings based on the use of two 15-foot lengths of 4/0 cable



TR-700BR

## DA-750 PORTABLE MAGNETIC INSPECTION UNIT

### TR700 TRANSPORT TRUCK

### ACCESSORY ITEMS

MA-7000	INDIVIDUAL PRODS (SET OF 2)
MA-7001	DUAL HORIZONTAL PROD ASSEMBLY
MA-7003	BRAIDED CONTACT CLAMP
MA-7EC	4/0 EITHEREND CONNECTOR
MA-7EL	4/0 EITHEREND/LUG ADAPTER
MA-7RC	20' REMOTE CONTROL CABLE ASSY
MA-7ST	REPLACEMENT PROD TIP (5 5/8")
MC-1540	15' 4/0 CABLE SET (W/LUG & EITHEREND)
MC-1541	15' 4/0 CABLE SET (W/EITHERENDS)
TR-700BR	CABLE EXTENSION BKT

## ACCESSORY ITEMS



**MA-7000**  
Individual Prods  
(set of 2)



**MA-7RC**  
Remote Switch Assembly  
(20')



**MA-7EL**  
4/0 Eitherend/Lug Adapter



**MA-7EC**  
4/0 Eitherend Connector



**MA-7001**  
Dual Horizontal Prod Assy  
(adjustable tips)



**MA-7003**  
Braided Contact Clamp  
(3 inch Grip)



**MA-7ST**  
Replacement Prod Tips  
(aluminum or copper)